


Index No. R 21

CASS COUNTY LAND CORNER RECORD

T. 141 R. 27 M. 5TH Coordinates: X _____ Y _____
NE 26 Corner common to sections R3, 24, 25, 26



EXISTING SURVEYS

Original Government Survey
Year surveyed 1874
Original monument POST

Original Evidence Found
Year of search _____ By _____
Monument found _____

Species	Bearing Trees			
	<u>CEGAR</u>	<u>CEGAR</u>	<u>CEGAR</u>	<u>CEGAR</u>
Diameter	<u>6"</u>	<u>6"</u>	<u>10"</u>	<u>8"</u>
Bearing	<u>N52W</u>	<u>N48E</u>	<u>S45E</u>	<u>S45W</u>
Distance	<u>14 LKS</u>	<u>24 LKS</u>	<u>30 LKS</u>	<u>9 LKS</u>

Original Bearing Trees Found			
Species	_____	_____	_____
Diameter	_____	_____	_____
Bearing	_____	_____	_____
Distance	_____	_____	_____

○ = Corner

Subsequent Corner Restoration
Year surveyed 1920 By LINCOLN MARKET
Location filed COUNTY BOOK "C" P. 378
Monument FIND OLD POST FIND B.T.: 7" CEDAR S53E 18.5'
SETTLERS IN AREA CLAIM THIS TO BE CORNER ACCEPTED FOR YEARS

Evidence of Subsequent Corner Restoration
Year of search _____ By _____

Bearing Trees, Reference Objects	
Species	<u>CEGAR</u> <u>CEGAR</u>
Diameter	<u>12"</u> <u>4"</u>
Bearing	<u>S56-15E</u> <u>N28-15W</u>
Distance	<u>41.3'</u> <u>30.0'</u>

Bearing Trees, Reference Objects	
Species	_____
Diameter	_____
Bearing	_____
Distance	_____

Subsequent Corner Restoration
Year surveyed _____ By _____
Location filed _____
Monument _____

Evidence of Subsequent Corner Restoration Found
Year of search _____ By _____
CERTIFICATE - BILL OKERMAN - 1969
Found 2" capped pipe; 12" Cedar
S56° 15' E 41.3' now 16"; 4" Cedar
N28° 15' W 30' downed. Set 2" x 5'
galvanized steel pipe filled with
concrete and capped with 3"
stamped brass tablet. Ties: 6" Cedar
N46° E 37'; 6" Cedar N25W 29.3';
6" Cedar S37W 24.3'; 7" Cedar S42E
57.7'.
1993 12-11 Found 2" x 5' galvanized steel pipe filled
w/ concrete and capped. Straightened. 12-11-93
placed monument upright. 5-4-94 Cert. Filed
by Terry Freeman, RLS 21367, Doc # 357309
Ties: 7" Cedar N46E 37.00 (1969 USFS BT); 7" Cedar
N25W 29.30 (1969 USFS BT); 7" Cedar S37W 24.30'
(1969 USFS BT); 8" Cedar S42E 57.70' (1969
U.S.F.S. BT).

Remonumentation certificate prepared _____
Filed at _____

By _____
Date _____