


T. 141 R. 31 M. 5TH Coordinates: X \_\_\_\_\_ Y \_\_\_\_\_  
ETTY 3 Corner common to sections 23



EXISTING SURVEYS

Original Government Survey

Year surveyed 1873  
Original monument POST

Original Evidence Found

Year of search \_\_\_\_\_ By \_\_\_\_\_  
Monument found \_\_\_\_\_

Species	Bearing	Tree	Distance
<u>N. PINE</u>	<u>N. PINE</u>		
<u>13"</u>	<u>16"</u>		
<u>574E</u>	<u>563W</u>		
<u>914S</u>	<u>386S</u>		

Species	Bearing	Tree	Distance
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

Subsequent Corner Restoration

Year surveyed 1914 By Garmen - Curo  
Location filed microfilm - roll 115 BK92 P.50  
Monument Find what seem to be orig B.T.'S (stumps)

Evidence of Subsequent Corner Restoration

Year of search 1962 By Schneider  
Registered Land Survey No. 2 indicates  
iron pipe monument. Found  
2" iron pipe.

Bearing Trees, Reference Objects

Species	Bearing	Distance
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____

Bearing Trees, Reference Objects

Species	Bearing	Distance
<u>R. Oak</u>	<u>R. Oak</u>	<u>Pine Stp.</u>
<u>6"</u>	<u>6"</u>	<u>30"</u>
<u>N39°E</u>	<u>N83°E</u>	<u>N58°E</u>
<u>43.6'</u>	<u>42.25'</u>	<u>23.25'</u>

C-17

Subsequent Corner Restoration

Year surveyed 9/03 By Landecker & Assoc.  
Location filed \_\_\_\_\_  
Monument Found 2" capped pipe in  
mound up 9", 11" ± SE of fence  
corner and witnessed.

<u>11" R. Oak</u>	<u>N39°E</u>	<u>44.12'</u>
<u>13" R. Oak</u>	<u>N83°E</u>	<u>42.63'</u>
<u>10" R. Oak</u>	<u>S3°W</u>	<u>22.55'</u>

A C of L was filed.

Evidence of Subsequent Corner Restoration Found

Year of search \_\_\_\_\_ By \_\_\_\_\_  
PLAT - REGISTERED LAND SURVEY #1, #2, #3  
R.F. SCHNEIDER 1972  
PLAT - SEVEN PINES  
R.F. SCHNEIDER 1973