

Index No. \_\_\_\_\_

CASS COUNTY LAND CORNER RECORD

T. \_\_\_\_\_ R. \_\_\_\_\_ M. \_\_\_\_\_ Coordinates: X \_\_\_\_\_ Y \_\_\_\_\_

Corner common to sections \_\_\_\_\_



= Corner

EXISTING SURVEYS

Original Government Survey

Year surveyed \_\_\_\_\_  
Original monument \_\_\_\_\_

Original Evidence Found

Year of search \_\_\_\_\_ by \_\_\_\_\_  
Monument found \_\_\_\_\_

Bearing Trees

Species \_\_\_\_\_  
Diameter \_\_\_\_\_  
Bearing \_\_\_\_\_  
Distance \_\_\_\_\_

Original Bearing Trees Found

Species \_\_\_\_\_  
Diameter \_\_\_\_\_  
Bearing \_\_\_\_\_  
Distance \_\_\_\_\_

Subsequent Corner Restoration

Year surveyed \_\_\_\_\_ By \_\_\_\_\_  
Location filed:  
Monument:

Evidence of Subsequent Corner Restoration

Year of search \_\_\_\_\_ By \_\_\_\_\_  
Location filed:  
Monument:

Bearing Trees, Reference Objects

Species \_\_\_\_\_  
Diameter \_\_\_\_\_  
Bearing \_\_\_\_\_  
Distance \_\_\_\_\_

Bearing Trees, Reference Objects

Species \_\_\_\_\_  
Diameter \_\_\_\_\_  
Bearing \_\_\_\_\_  
Distance \_\_\_\_\_


Subsequent Corner Restoration

Year surveyed \_\_\_\_\_ By \_\_\_\_\_  
Location filed:  
Monument:

Evidence of Subsequent Corner Restoration Found

Year of search \_\_\_\_\_ By \_\_\_\_\_  
Location filed:  
Monument:

T. 143 R. 27 M. 5th Coordinates: X \_\_\_\_\_ Y \_\_\_\_\_  
E44 30 Corner common to sections 29/30



EXISTING SURVEYS

**Original Government Survey**

Year surveyed 1873  
Original monument lost

**Bearing Trees**

Species	<u>Tam</u>	<u>Tam</u>	_____
Diameter	<u>6"</u>	<u>8"</u>	_____
Bearing	<u>N64E</u>	<u>S80W</u>	_____
Distance	<u>20 LKS</u>	<u>15 LKS</u>	_____

**Original Evidence Found**

Year of search \_\_\_\_\_ By \_\_\_\_\_  
Monument found \_\_\_\_\_

**Original Bearing Trees Found**

Species	_____	_____	_____
Diameter	_____	_____	_____
Bearing	_____	_____	_____
Distance	_____	_____	_____

**Subsequent Corner Restoration**

Year surveyed 1928 By GLD  
Location filed Sec of State  
Monument Testimony of local residents - Set w.c. on N. bank of ditch on N. side road alongside 3x6x50" cedar post set 1x36" i.p. w/brass cap  
wc  
14  
1928

**Bearing Trees, Reference Objects**

Species	<u>Cedar</u>	<u>Birch</u>	_____
Diameter	<u>12"</u>	<u>8"</u>	_____
Bearing	<u>N27 1/2 E</u>	<u>N8 1/4 W</u>	_____
Distance	<u>275 LKS</u>	<u>350 LKS</u>	_____

**Evidence of Subsequent Corner Restoration**

Year of search 1975 By Co Hwy Dept  
Co Rd #4  
Corner

**Bearing Trees, Reference Objects**

<u>Steel Post</u>	<u>steelpost</u>	<u>steelpost</u>	_____
<u>SE</u>	<u>South</u>	<u>SW</u>	_____
<u>169.31</u>	<u>158.2'</u>	<u>159.26'</u>	_____

**Subsequent Corner Restoration**

Year surveyed \_\_\_\_\_ By \_\_\_\_\_  
Location filed \_\_\_\_\_  
Monument \_\_\_\_\_

**Evidence of Subsequent Corner Restoration Found**

Year of search \_\_\_\_\_ By \_\_\_\_\_  
PLAT - Block 5 Bar River  
MARTIN KJOZHANG 1916

1986 Certificate - Walter Curo  
Doc. # 291487  
Set 2" x 36" galvanized iron pipe with brass cap down 8" below surface of Co. Rd #4.

4/99 J. FOSTER  
Brass capped pipe placed at above location  
Steel signpost N44°W 15.96m  
Power pole N17°W 11.040m  
Steel signpost N42°E 15.209m

Certificate of location 5/05/99  
Doc. No. 412419